

The ADFS Huntsville Regional Laboratory needs to replace one (1) 7.5 ton roof HVAC unit.

Specifications:

Disconnect and remove existing 7.5 ton roof top unit

Install one (1) *Carrier 7.5 ton roof top HVAC unit (no equal)

Install new 60 amp fused high voltage disconnect and electrical wiring

Install new drain piping

Install one (1) smoke detector mounted in return duct

Warranty- 5 years on compressor, 1 year labor, 1 year parts

All installation labor

Crane rental to remove old unit and install new unit

* Note: Needs to be a Carrier brand HVAC unit so it matches all the other Carrier brand HVAC units in the building.